

Grout Scouts, Inc.

2326 Harper Lane
Fort Madison, IA 52627
319.721.5047

Rusty Sands
Director of Public Works
111 West Franklin St
Bloomfield, IA 52537

May 20, 2026

Mr. Sands,

Thank you for considering Grout Scouts, Inc. for the corrugated metal pipe maintenance for the City of Bloomfield. Grout Scouts, Inc. will provide all supervision, labor, and specialty equipment for the repair. The City will provide location of utilities, excavation, material, and traffic control as needed.

30" CMP on South West Street about ¼ miles north of HWY 2

GSI will install a 26" x approximately 94' Spiral Wound Liner at \$65.00 per foot:	\$6,110.00
Labor to prepare the CMP for installation and to fill the annular space will take about 12 hours at \$365.00 per hour:	4,380.00
Mobilization will be:	\$400.00

Estimated Material Cost to City

Two yards of M4 concrete at 250.00 per yard:	500.00
6 yards of grout at 300.00 per yard:	1,800.00

Proposal Acceptance

Richard Lovett President Grout Scouts, Inc.	Date	Rusty Sands Director of Public Works The City of Bloomfield, Iowa	Date
---	------	---	------

Thanks for the Opportunity!!!