

# N.A.P. co.



## NORRIS ASPHALT PAVING

8/17/2023

Blomfield, City of  
Attn: Rusty Sands

RE: Rebecca, Nevelle, and Howard

Rusty

The crew will start by milling butt joints and grinding, shaping, and recompacting the two blocks on Howard at a depth approximately 4-6 inches. There is a small partial depth patch at the intersection of Howard and Jefferson that will be paved in at a compacted depth of 2 inches. Howard will be paved back with a compacted depth of 3 inches along with Nevelle. Rebecca will be overlaid with 4 inches of hot mix asphalt (HMA). If you have any questions, please give me a call.

	Description	Approx. Units	Cost Per Unit	Extension
1	Milling, Blading, Recompacting, Prep	1 Lump Sum	\$17,500.00	\$17,500.00
2	4,3 and 2 Inch HMA Paving	1,040 Ton	\$160.00	\$166,400.00
				\$ 0.00
				\$ 0.00
			<b>TOTAL</b>	<b>\$183,900.00</b>

Quote valid for 30 days.

All quantities are estimated, actual quantities will prevail.

Quote includes all equipment, labor, and materials to complete project as described.

Net 30 days. Interest will be accrued @ 1.5% per month on balances over 30 days.

If accepted, please sign, date, and return one copy to NAP Co. Your project will be scheduled as permitted by our Commercial Crew. Thank you!

Accepted: \_\_\_\_\_ Date: \_\_\_\_\_

Thank you for the opportunity to quote your project. If you have any questions about the above quote, please give us a call.

Respectfully submitted,

T.J. Blain  
Commercial Sales



**- Proposal & Contract -**

**CENTRAL ASPHALT PAVING INC.**  
540 NE 46<sup>th</sup> Place Des Moines, IA 50313  
Phone (515) 262-5106 | Fax: (515) 265-6752  
office@centralasphalt paving.com

DATE: August 14, 2023

**Bloomfield, City of**  
( Company Name )  
**Bish, Brandon**  
( Proposal Submitted To )  
**111 W. Franklin St.**  
( Address )  
**Bloomfield, IA 52537**  
( City, State, Zip )

**641 664-2260**  
(Telephone)

(Telephone)

**641 208-5899**  
(Cell or Mobile Phone)

(Fax)

**2 City Blocks**  
( Job Site/Project )  
**Brandon Bish**  
( Job Site Contact )  
**Howard St.**  
( Job Address Line 2 )

**Bloomfield, IA**  
( City, State, Zip )

**brandon.bish@cityofbloomfield.org**

**We hereby submit specifications and estimates for:**

- #1. Between Locust & Jefferson:**  
We will clean, tack, and lay approx. 40 tons of leveling, more, or less @ a price of \$184.36 per ton.  
We will then lay a 2" inch average depth over 6,693' Sq Ft. (291x23) this calls for 82 tons.  
**Between Jefferson & Franklin:**  
We will clean, tack, and lay approx. 40 tons of leveling, more, or less @ a price of \$184.36 per ton.  
We will then lay a 2" inch average depth over 6,744' Sq Ft (307x22) this calls for 83 tons.  
**We will do all this for a cost of \$45,168.80, this is @ a cost of \$184.36 per ton.**
- #2.** We can also mill 4 butt-joints at the end of each block to match in.  
**We will do this for an additional cost of \$4,350.00.**
- #3. Rebecca drive:**  
We will clean, tack, and lay approx. 100 tons of leveling, more, or less @ a price of \$184.36 per ton.  
We will then lay a 2" inch average depth over 24,752' Sq Ft this calls for approx 303 tons.  
**We will do this for a cost of \$74,297.08.**  
**OR-** We will lay a 3" inch average depth calling for approx. 454 tons.  
**We will do this for a cost of \$102,135.44.**  
**OR-** We will lay a 5" inch average depth calling for approx. 757 tons.  
**We will do this for a cost of \$ 157,996.52.**
- #4. Nevell Ave:**  
We will clean, tack, level, and lay approx. 30 tons of leveling more or less @ a price of \$184.36 per ton.  
We will then lay a 2" inch average depth over 8,917' Sq Ft. this calls for approx. 109 tons.  
**We will do this for a cost of \$25,626.04.**

*Thank you for considering Central Asphalt Paving, Inc*

**Lary Churchill Estimator 515 975-6477**